BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17883

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/01/2015-16

Providing Sodium Fittings & Electrical Fittings to the areas of Ward No.8, Kodigehalli Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S N PRADEEP KUMAR	
				In Figures	In Words
1	108	Supplying High pressure sodium vapour street light luminaire suitable for use with high pressure sodium vapour lamp with integrated control gear and grey colr powder coated. The fitting shall be non corrosive pressure die cast aluminium housing with high purity anodized aluminium housing with EPDM Gaskets suitable for Outer Dia of pole 40 mm -60 mm. Cable entry through a cable gland with toggle clips. IP65 protection for both optical & electrical compartment. Bottom cover may be with poly carbonate/tempered/ toughened glass.Luminaire efficiency should be > 60 % and ambient temperature >35 deg C. High Intensity Discharge electro magnetic ballast with copper winding of Orthocyclic winding coil. Class H insulated dual coated copper wire. Complaince to IEC 61347-2-9 Safety & IEC 60923-Performance. Winding Temperature rise " T=70 deg C. Luminaire shall be suitable to operate on 230/250 V 50 Hz AC supply finish including wiring , Ignitor, condenser, SS Toggles for opening front hingeable glass 250 Wattsa) Group 'A'	Each	6035.0	Rupees Six Thousand Thirty Five Only
2	38	Supplying and Fixing 50mm class A GI pipe up to 4.5 mtrs. long with a reducing collar of 50x40mm to which, an extension of 250 mm pipe is fixed for 125 or 250/400 watts MV / sodium vapour street light fitting, using suitable clamps, bolts ,nuts, and wiring using suitable capacity wires.	Each	1250.0	Rupees One Thousand Two Hundred Fifty Only
3	70	Supplying and Fixing of.....mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires. 17.1.2)Using 32mm dia G.I.pipe	Each	405.0	Rupees Four Hundred Five Only
4	750	Supplying of 1.1 KV grade Aerial Bunched Cable Stranded and Compacted Aluminium Phase Conductor and Stranded Messenger Conductor with all aluminium Alloy, Phase Conductor is insulated with XLPE Compound, Insulated Messanger with SpecifiedIS-14255:1995 & confirming to GTP of Group A 2X16+1X25Sqmm	mtr	72.0	Rupees Seventy Two Only
5	750	Striniging of 1.1 KV grade aerial bunched 3 core cable of XLPE insulation standard aluminium conductor standard around a weather resistant black XLPE insulated AAA messanger wire (3X 25 Sq mm + 1X 16 sqmm + 1X 25Sqmm + 1X 35 sqmm)	Mtr	8.0	Rupees Eight Only
6	5	Dead End Clamp/ Anchor clamps assembly 25 to 95 sqmm bear messanger (Standard Stock materials 2010-11)	Nos	140.0	Rupees One Hundred Forty Only
7	38	suspension clamp assemblly 25 to 95 sqmm bear messanger (Standard Stock materials 2010-11)	Nos	196.0	Rupees One Hundred Ninety Six Only
8	38	Errection of suspension clamp 25 to 95 sqmm bear messanger (Labour charges 2010-11)	Nos	74.0	Rupees Seventy Four Only

For GANGA ENTERPRISES

Proprietor

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S N PRADEEP KUMAR	
				In Figures	In Words
9	5	Errection of Anchor clamp 25 to 95 sqmm bear messanger (Labour charges 2010-11)	Nos	59.0	Rupees Fifty Nine Only
10	38	Supply and fixing of ..... cross arm including all Hardwares compete as per the standard technical specification.b) 2 Pin 45x45x5mm-510mm	Each	285.0	Rupees Two Hundred Eighty Five Only
11	12	Fixing halogen/metal halide/SVL/IL /LED floodlight fitting over existing pole/wall ceiling including clamps ,bolts ,nuts and wiring using suitable capacity wires complete . Labour charges for releasing of material shall be at 90 % of the cost of erection . Rate of fixing is Rs.176.00 =0.9 X 306.00=158.4 Therefore 176.00+158.40=334.40	Each	52.0	Rupees Fifty Two Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

29/1/16